Sectt. II-27—50,006—27-10-41.

Public Works **(194 2 ) Department**

**M. SERIES.**

**G.O. No.** 4640

**Dated** the 16th December 1942

---

**[Despatch Abstract.]**

Buildings Coimbatore District - Kollegal - Quarters of the Inspector of Police - Repairing with Mangalore tiles - Expenditure Rs. 1500/- Approved.

C.F. 32 (a).

POLICE Department

From (Name) L.B. GAGSON, ESQUIRE

Designation Inspr -Genl. of Police,

Station Madras.

Received UNDER SECRETARY TO GOVERNMENT 29 NOV 1942 HOME DEPT. Registered

To

The Secretary to Government,
Government of Madras,
HOME DEPARTMENT.

28348/43
30/11/42

Enclosures:

No. Re 415-1/42 dated 28th November 1942.

Sir,

SUB:--Buildings--Coimbatore district--Kollegal--Circle Inspector's quarters--Reroofing with Mangalore tiles--Estimate submitted.

---

I have the honour to submit, for the approval of the Government, an estimate amounting to Rs. 1500/- for reroofing the quarters of the Inspector of Police, Kollegal Circle, in the Coimbatore district

2. The report accompanying the estimate explains the necessity for, and the nature of, the work. I enclose for reference, a sketch showing the position of the quarters I consider that, in order to prevent the monkeys damaging the tiles and to avoid having to renew them frequently, the present country pot tiles should be replaced by Mangalore tiles which will be cheaper in the long run.

3. The Executive Engineer reports that the work will

(P.T.O.)

will increase the capital cost of the building by Rs.16/- rent data statement is also enclosed.

4. The work will be carried out by the Public Works Department and the cost met by them from their lump sum grant.

5. As the work is urgent, I request the early orders of Government.

I have the honour to be,
Sir,
Your most obedient Servant,

for Inspr.-Genl. of Police.

KVS.27.11.

Annexure X.

Home Dept.

No iron, steel and teakwood are involved. Orders whether the proposal may be accepted. If so the file may be sent to P.W.D. for issue of orders.

7/12/42

2.12.42

UNDER SECRETARY TO GOVERNMENT
7-DEC 1942
UNDER SECRETARY TO GOVERNMENT
7-12-42
V
DEC 1942
4846
PUBLIC WORKS DEPARTMENT

Report to accompany the estimate 'Replacing pot tiled roof over Circle Inspector's quarters at Kollegal with the Mangalore tiles Estimate Rs.1500/-

This estimate is ~~proposed~~ as per requisition of the District Superintendent of Police, Coimbatore in letter No.2709 dated 25th.

This estimate provides for re-roofing the buildings whose existing roofs are of country pot tiles and Mangalore tiles. Those tiles are disturbed and broken by monkeys necessitating very frequent repairs. It is considered that it would be cheaper in the long run to replace them by Mangalore tiles.

The present proposals are as follows:

5.Stable. Plain pot tiled roofing ~~with~~ will be replaced by Mangalore tiled roof. Provision is also made for renewing some of the rotten roof timbers.

Other petty repairs also will be effected for the proper upkeep of the building.

The amount that will go to increase the capital cost of the building will be Rs.16/-

Executive Engineer,
Salem Division.

cing pot tiled roof over circle Inspector's quarters at Kollegal with Mangalore tiles--Estimate Rs. ~~1,250/-~~ 1500/-

5

## ESTIMATE FORM- Abstract.

| Item number. (1) | Quantity. (2) | Description of work. (3) | Rate. (4) | Per (5) | Amount. (6) | Total. (7) |
|---|---|---|---|---|---|---|
| | | | RS. | | RS. | RS. |
| 1. | 3200. | Dismantling pot and flat tiled roof without roof timbers and carefully stacking materials useful for reuse. | 0/14. | 100 sft. | 28. | |
| 2. | 1110. | Dismantling pot tiled roof with out roof timbers and carefully stacking materials useful for re-use. | 0/9. | " | 6. | |
| 3. | 2020. | Best tiled roofing with Mangalore tiles II class set in lime mortar over flat tiles less cost of tiles and reepers including wind ties and lime mortar borders. | 8/4 | " | 167 | |
| 4. | 2300. | Best tiled roofing with Mangalore tiles on old reepers, less cost of tiles, including wind ties and lime mortar borders. | 4/15 | " | 114 | |
| 5. | 6500 | Supplying best Mangalore tiles II class at site of work. | 91/5 | 1000 Nos. | 594 | |
| 6. | 290. | Supplying Mangalore tiled ridge tiles II class. | 0/6. | Each | 109 | |
| 7. | 21.00 | Country wood wrought and put up. | 4/- | 1 cft. | 84 | |
| 8. | 500 | Plastering with lime mortar(1:2) ½" thick after raking out old plaster. | 2/15 | 100 sft. | 15 | |
| 9. | L.S. | Painting the new wood work. | L.S. | | 3 | |
| 10. | 500 | Supplying new country wood reepers 2" x 1" | 2/15 | 100 rft. | 15 | |
| 11. | L.S. | Fixing old teak reepers 2" x ½" one over the other i.e. 2"x 1" to suit ordinary Mangalore tiled roofing and new teakwood reepers. | | | | |
| 12. | | Removing the old wood work and refixing the same after necessary levelling etc. | L.S. | | 30 | |
| 13. | | Country brick in lime mortar for cornice work at the end of the roof gables. | | | | |
| 14. | | Petty supervision and contingencies. | | | 47 | |
| | | | | | 1212 | |
| | | Add extra 25%. | | | 306 | |
| | | | | | 1518 | |
| | | Credit for old materials. | | | 18 | |
| | | | Net. | | 1500 | |

N.B. This will increase the capital cost of the building by Rs. 16/-

Grand total of estimate

6/9 — I. [illegible]

*Executive Engineer.* G. [illegible] Contractor

Salem Division. 3/4

PLR 19/10/42

Dist. Supdt. of Police

P.W.D. V-14 —17,583—41/-41.

E. No. 32.

CIRCLE— Coimbatore.

DIVISION— Salem

DISTRICT— Coimbatore.

TALUKS (OR ESTATE IN CASE OF ESTATE WORKS)

Kollegal

## ESTIMATE FORM—Abstract.

Section— B & R.

Major head— 50 C.W.P.

Minor head— Original works

Detailed or service head— police.

Departmental head—

Project of which the work forms part—

Name of work— Replacing pot tiled roof over Circle Inspector's quarters at Kollegal with Mangalore tiles- Item No.8 in the Register of Buildings.

Amount of estimate, Rs. 1,500/

To be carried out by— P.W.D.

REFERENCES.

Report to accompany the estimate 'Replacing pot tiled roof over Circle Inspector's quarters at Kollegal with the Mangalore tiles' Estimate Rs.1500/-

This estimate is ~~proposed~~ prepared as per requisition of the District Superintendent of Police, Coimbatore in letter No.2709 dated 25th May 42

This estimate provides for re-roofing the buildings whose existing roofs are of country pot tiles and Mangalore tiles. These tiles are disturbed and broken by monkeys necessitating very frequent repairs. It is considered that it would be cheaper in the long run to replace them by Mangalore tiles.

The present proposals are as follows:

1. The roof of main building and kitchen are of pot tiles over flat tiles. It is now proposed to retile the roof of the main building only with Mangalore tiles over flat tiles and that of the kitchen block with plain Mangalore tiles without flat tiles.

2. Kitchen block. As some of the roof timbers are bad, necessary provision is made to renew them. As 2" x 1" reepers are required for plain Mangalore tile roofing it is proposed to remove the existing 2" x ½" reepers and refix them at suitable intervals one over the other thus making up 2" x 1" Lump sum provision is also made for rectifying sags in roofs.

3. Covered passage. The existing roof is with plain pot tiles and the proposal to reroof it with plain Mangalore tiles. One of the wooden posts will be renewed.

4. Latrine and fire wood room. The existing plain pot tiled roofs will be replaced by Mangalore tiled roofing.

5. Stable. Plain pot tiled roofing ~~with~~ will be replaced by Bangalore tiled roof. Provision is also made for renewing some of the rotten roof timbers.

Other petty repairs also will be effected for the proper upkeep of the building.

The amount that will go to increase the capital cost of the building will be Rs.16/-

Executive Engineer,
Salem Division.

19/10/42

Replacing pot tiled roof over circle Inspector's quarters at Kollegal with Mangalore tiles-Estimate Rs. ~~1,250/-~~ 1500/-

9

## ESTIMATE FORM—Abstract.

1945

| Item number. (1) | Quantity. (2) | Description of work. (3) | Rate. (4) | Per (5) | Amount. (6) | Total. (7) |
|---|---|---|---|---|---|---|
| | | | RS. | | RS. | RS. |
| 1. | 3200 | Dismantling pot and flat tiled roof without roof timbers and carefully stacking materials useful for reuse. | 0/14. | 100 sft. | 28. | |
| 2. | 1110. | Dismantling pot tiled roof without roof timbers and carefully stacking materials useful for re-use. | 0/9. | | 6. | |
| 3. | 2020 | Best tiled roofing with Mangalore tiles II class set in lime mortar over flat tiles less cost of tiles and reepers including wind ties and lime mortar borders. | 8/4 | | 167 | |
| 4. | 2300 | Best tiled roofing with Mangalore tiles on old reepers, less cost of tiles, including wind ties and lime mortar borders. | 4/15 | " | 114 | |
| 5. | 6500 | Supplying best Mangalore tiles II class at site of work. | 91/5 | 1000 Nos. | 594 | |
| 6. | 290 | Supplying Mangalore tiled ridge tiles II class. | 0/6. | Each | 109 | |
| 7 | 21.00 | Country wood wrought and put up. | 4/- | 1 cft. | 84 | |
| 8 | 500 | Plastering with lime mortar(1:2) ½" thick after raking out old plaster. | 2/15 | 100 sft. | 15 | |
| 9. | L.S. | Painting the new wood work. | | | 3 | |
| | 500 | Supplying new country wood reepers 2" x 1". | 2/15 | 100 rft. | 15 | |
| 11. | L.S. | Fixing old teak reepers 2" x ½" one over the other i.e. 2"x 1" to suit ordinary Mangalore tiled roofing and new teakwood reepers. | | | | |
| 12. | | Removing the old wood work and refixing the same after necessary levelling etc. | L.S. | | 30. | |
| 13. | | Country brick in lime mortar for cornice work at the end of the roof gables. | | | | |
| 14. | | Petty supervision and contingencies. | | | 47 | |
| | | | | | 1212 | |
| | | Add extra 25%. | | | 306 | |
| | | | | | 1518 | |
| | | Credit for old materials. | | | 18 | |
| | | | Net. | | 1500 | |

N.B. This will increase the capital cost of the building by Rs. 16/-

Grand total of estimate

Executive Engineer.
Salem Division.

Countersigned

Dist. Supt. of Police
Kollegal Communication

PVB 14/10/42

P.W.D. V-14 —17,58.

**E. No. 32.**

CIRCLE— Coimbatore.

DIVISION— Salem

DISTRICT— Coimbatore.

TALUKS (OR ESTATE IN CASE OF ESTATE WORKS).

Kollegal.

## ESTIMATE FORM—Abstract.

Section— B & R.

Major head— 50 C.W.P.

Minor head— Original work

Detailed or service head— Police.

Departmental head—

Project of which the work forms part—

Name of work— Replacing pot tiled roof over Circle Inspector's quarters at Kollegal with Mangalore tiles- Item No.8 in the Register of Buildings.

Amount of estimate, Rs. 1,500/-

To be carried out by— P.W.D.

### REFERENCES.

12 21/12 21/12

## DRAFT FOR APPROVAL.

P.W. Dept

| | Date. | Initials. |
|---|---|---|
| When received for fair copying .. | | |
| When copied .. | | |
| When examined.. | | |
| When signed . | | |
| When despatched. | | |

SUBJECT :— Buildings - Coimbatore Dist - Kollegal. Quarters of the Inspector of Police - Re-roofing with Mangalore tiles - Expn - Rs 1500/- Approved

READ AGAIN _____, dated _____ 19____.

" " _____ _____ 19____.

READ *ALSO* :—

No. 8462/Ser From the I. G. of Police, No. 1015-1/1093/Ser dated 28.11. 1942. Hy-1-12

" _____ " _____ " _____ " _____ 19____.

" _____ " _____ " _____ " _____ 19____.

~~Order~~ ~~Resolution~~ Ms. ~~Rout.~~ No. 4640, dated 16 — 12 — 1942.

Fin(Exp B)

The draft order overleaf may be accepted and the case returned to Revs

Fin no. 23498(0)Exp B
13-12-42